



TRANSFORMER TEST REPORT

BEFORE AND AFTER MAINTENANCE

(OLTC Service)

**SPAJ Electrical
Engineering (M) Sdn. Bhd.**

COMPANY PROPRIETARY INFORMATION

This document has been prepared for the recipient and contains information that is proprietary to **SPAJ Electrical Engineering (M) Sdn Bhd**. Unless otherwise stated in writing, **SPAJ Electrical Engineering (M) Sdn Bhd** reserves all the rights to its contents including, but not limited to, all competitor's information, creative and design proposal, information provided, whether as part of a evaluation process, general documentation or budget proposal is for the proposed project and is not to be disclosed, distributed or used in whole, or in part.

www.spaj.biz

Engaging trust, empower solution

TRANSFORMER TESTING REPORTS

Location: PPU MALAYSINO

Job: T2 BEFORE SERVICE

Date: 28/09/2024

TRANSFORMER NO	: 02
SERIAL NO	: 30001
VOLTAGE	: 33000/22000
KVA	: 30000
MANUFACTURE	: MTM
YEAR	: 2010
TESTING DATE	: 28/09/2024

TEST PERFORMED

S.NO .	TITLE
1	TANDELTA WINDING
2	EXCITATION CURRENT 10KV
3	TURN RATIO MEASUREMENT
4	DC WINDING RESISTANCE
5	OLTC DYNAMIC CURRENT MEASUREMENT
6	INSULATION RESISTANCE / POLARIZATION INDEX

TEST EQUIPMENT USED :

1. MEGGER TDX 120
2. MEGGER TRAX 220
3. MEGGER MIT515 INSULATION TESTER,

TESTING PERFORMED BY:

1. VICKNESH A/L SUBRAMANIAM
2. GOBINATH RAJU
3. SAKTHI




TRANSFORMER TANDELTA TEST REPORT


*SPAJ Electrical
Engineering (M) Sdn. Bhd.*



Tan Delta - Power Transformer

Designation	Test Mode	f (Hz)	U	I eq	C	%TD at 40 °C	ITC2 Corr. Factor	Corr. %TD to 20°C	P eq at 40 °C	% VDF	ITC2
CHG + CHL	GST-GND	50.00	9.999 kV	53.73 mA	17.10 nF	0.401	0.907	0.364	2.154 W	0.02 %	
CHG	GSTg-RB	50.00	10.01 kV	8.481 mA	2.700 nF	0.823	0.907	0.746	697.7 mW	0.06 %	●
CHL	UST-R	50.00	10.01 kV	45.25 mA	14.40 nF	0.308	0.907	0.279	1.393 W	0.02 %	
CLG + CLH	GST-GND	50.00	6.601 kV	72.83 mA	23.18 nF	0.343	0.907	0.311	2.500 W	0.02 %	
CLG	GSTg-RB	50.00	6.608 kV	27.59 mA	8.782 nF	0.383	0.907	0.347	1.057 W	0.02 %	
CLH	UST-R	50.00	6.608 kV	45.25 mA	14.40 nF	0.308	0.907	0.279	1.394 W	0.01 %	





Comment:



TRANSFORMER EXCITATION 10KV TEST REPORT

SPAJ Electrical
Engineering (M) Sdn. Bhd.



Tan Delta - Power Transformer Excitation

Connection	Tap	Tap Voltage (V)	f (Hz)	U	I eq	L	P eq at 48 °C
A-B	1	36 310	50.00	10.06 kV	66.34 mA	757.4 H	513.2 W
B-C	1	36 310	50.00	9.974 kV	29.72 mA	1.794 kH	238.5 W
C-A	1	36 310	50.00	10.03 kV	60.58 mA	877.7 H	485.3 W
A-B	2	35 759	50.00	9.988 kV	68.31 mA	735.0 H	528.3 W
B-C	2	35 759	50.00	10.02 kV	30.33 mA	1.768 kH	244.1 W
C-A	2	35 759	50.00	9.978 kV	61.96 mA	857.8 H	496.2 W
A-B	3	35 207	50.00	9.980 kV	70.02 mA	718.6 H	542.3 W
B-C	3	35 207	50.00	9.997 kV	31.05 mA	1.738 kH	250.7 W
C-A	3	35 207	50.00	10.01 kV	63.41 mA	840.0 H	508.4 W
A-B	4	34 656	50.00	10.02 kV	71.60 mA	704.5 H	555.5 W
B-C	4	34 656	50.00	9.994 kV	31.77 mA	1.712 kH	257.6 W
C-A	4	34 656	50.00	9.973 kV	65.01 mA	823.5 H	522.7 W
A-B	5	34 105	50.00	10.03 kV	73.39 mA	690.0 H	570.8 W
B-C	5	34 105	50.00	10.02 kV	32.55 mA	1.686 kH	265.1 W
C-A	5	34 105	50.00	9.977 kV	66.69 mA	806.3 H	537.4 W
A-B	6	33 553	50.00	10.04 kV	75.17 mA	676.8 H	586.4 W
B-C	6	33 553	50.00	10.01 kV	33.40 mA	1.659 kH	273.5 W
C-A	6	33 553	50.00	10.02 kV	68.39 mA	790.0 H	552.6 W
A-B	7	33 002	50.00	10.02 kV	77.15 mA	663.2 H	604.0 W
B-C	7	33 002	50.00	9.988 kV	34.36 mA	1.631 kH	282.8 W
C-A	7	33 002	50.00	10.00 kV	70.23 mA	774.3 H	569.5 W
A-B	8	32 451	50.00	10.03 kV	79.14 mA	650.3 H	621.8 W
B-C	8	32 451	50.00	10.04 kV	35.30 mA	1.608 kH	292.3 W
C-A	8	32 451	50.00	10.03 kV	72.14 mA	759.1 H	587.0 W
A-B	9	31 899	50.00	10.05 kV	81.32 mA	637.1 H	641.7 W
B-C	9	31 899	50.00	9.973 kV	37.98 mA	1.394 kH	303.5 W
C-A	9	31 899	50.00	10.02 kV	74.27 mA	743.1 H	606.7 W
A-B	10	31 348	50.00	9.977 kV	84.71 mA	600.4 H	660.7 W
B-C	10	31 348	50.00	10.02 kV	38.92 mA	1.369 kH	312.0 W
C-A	10	31 348	50.00	9.987 kV	77.70 mA	688.9 H	624.7 W
A-B	11	30 797	50.00	9.989 kV	86.91 mA	587.6 H	679.6 W
B-C	11	30 797	50.00	9.980 kV	40.00 mA	1.339 kH	321.8 W
C-A	11	30 797	50.00	10.01 kV	79.80 mA	674.4 H	643.4 W
A-B	12	30 245	50.00	9.959 kV	89.35 mA	574.5 H	701.0 W

Connection	Tap	Tap Voltage (V)	f (Hz)	U	I eq	L	P eq at 48 °C
B-C	12	30 245	50.00	10.04 kV	41.06 mA	1.319 kH	332.2 W
C-A	12	30 245	50.00	10.00 kV	82.01 mA	660.4 H	663.5 W
A-B	13	29 694	50.00	10.02 kV	91.72 mA	562.5 H	721.9 W
B-C	13	29 694	50.00	10.02 kV	42.34 mA	1.292 kH	344.3 W
C-A	13	29 694	50.00	9.993 kV	84.46 mA	645.3 H	685.6 W
A-B	14	29 143	50.00	10.04 kV	94.28 mA	550.6 H	744.8 W
B-C	14	29 143	50.00	9.955 kV	43.74 mA	1.263 kH	357.5 W
C-A	14	29 143	50.00	9.997 kV	86.97 mA	631.6 H	708.8 W
A-B	15	28 591	50.00	10.06 kV	96.99 mA	538.8 H	769.3 W
B-C	15	28 591	50.00	9.974 kV	45.23 mA	1.241 kH	372.5 W
C-A	15	28 591	50.00	10.02 kV	89.61 mA	617.5 H	733.0 W
A-B	16	28 040	50.00	10.03 kV	100.1 mA	526.5 H	797.2 W
B-C	16	28 040	50.00	10.03 kV	47.38 mA	1.206 kH	393.5 W
C-A	16	28 040	50.00	10.01 kV	92.53 mA	603.0 H	759.9 W

Comment:



TRANSFORMER TURNS RATIO TEST REPORT

*SPAJ Electrical
Engineering (M) Sdn. Bhd.*




Turns ratio measurements

Connection	Tap (P)	Tap Voltage (V)	U	Test frequency	TTR	Measured TTR	Error	I Exc	Phase
A-B / a-n	1	36 310	125.0 V	50.00 Hz	2.859	2.852	-0.24 %	1.419 mA	0.0 °
B-C / b-n	1	36 310	125.0 V	50.00 Hz	2.859	2.852	-0.24 %	1.108 mA	0.0 °
C-A / c-n	1	36 310	125.0 V	50.00 Hz	2.859	2.852	-0.24 %	1.476 mA	0.0 °
A-B / a-n	2	35 759	125.0 V	50.00 Hz	2.815	2.809	-0.21 %	1.456 mA	0.0 °
B-C / b-n	2	35 759	125.0 V	50.00 Hz	2.815	2.809	-0.21 %	1.131 mA	0.0 °
C-A / c-n	2	35 759	125.0 V	50.00 Hz	2.815	2.809	-0.21 %	1.520 mA	0.0 °
A-B / a-n	3	35 207	125.0 V	50.00 Hz	2.772	2.767	-0.18 %	1.499 mA	0.0 °
B-C / b-n	3	35 207	125.0 V	50.00 Hz	2.772	2.767	-0.19 %	1.160 mA	0.0 °
C-A / c-n	3	35 207	125.0 V	50.00 Hz	2.772	2.767	-0.19 %	1.560 mA	0.0 °
A-B / a-n	4	34 656	125.0 V	50.00 Hz	2.728	2.724	-0.16 %	1.544 mA	0.0 °
B-C / b-n	4	34 656	125.0 V	50.00 Hz	2.728	2.724	-0.16 %	1.195 mA	0.0 °
C-A / c-n	4	34 656	125.0 V	50.00 Hz	2.728	2.724	-0.16 %	1.594 mA	0.0 °
A-B / a-n	5	34 105	125.0 V	50.00 Hz	2.685	2.682	-0.13 %	1.588 mA	0.0 °
B-C / b-n	5	34 105	125.0 V	50.00 Hz	2.685	2.681	-0.13 %	1.230 mA	0.0 °
C-A / c-n	5	34 105	125.0 V	50.00 Hz	2.685	2.681	-0.13 %	1.636 mA	0.0 °
A-B / a-n	6	33 553	125.0 V	50.00 Hz	2.642	2.639	-0.10 %	1.626 mA	0.0 °
B-C / b-n	6	33 553	125.0 V	50.00 Hz	2.642	2.639	-0.10 %	1.265 mA	0.0 °
C-A / c-n	6	33 553	125.0 V	50.00 Hz	2.642	2.639	-0.10 %	1.685 mA	0.0 °
A-B / a-n	7	33 002	125.0 V	50.00 Hz	2.598	2.596	-0.07 %	1.673 mA	0.0 °
B-C / b-n	7	33 002	125.0 V	50.00 Hz	2.598	2.596	-0.07 %	1.299 mA	0.0 °
C-A / c-n	7	33 002	125.0 V	50.00 Hz	2.598	2.596	-0.07 %	1.738 mA	0.0 °
A-B / a-n	8	32 451	125.0 V	50.00 Hz	2.555	2.554	-0.04 %	1.727 mA	0.0 °
B-C / b-n	8	32 451	125.0 V	50.00 Hz	2.555	2.554	-0.04 %	1.329 mA	0.0 °
C-A / c-n	8	32 451	125.0 V	50.00 Hz	2.555	2.554	-0.04 %	1.788 mA	0.0 °
A-B / a-n	9	31 899	125.0 V	50.00 Hz	2.511	2.511	-0.01 %	1.782 mA	0.0 °
B-C / b-n	9	31 899	125.0 V	50.00 Hz	2.511	2.511	-0.01 %	1.366 mA	0.0 °
C-A / c-n	9	31 899	125.0 V	50.00 Hz	2.511	2.511	-0.01 %	1.847 mA	0.0 °
A-B / a-n	10	31 348	125.0 V	50.00 Hz	2.468	2.469	0.03 %	1.842 mA	0.0 °
B-C / b-n	10	31 348	125.0 V	50.00 Hz	2.468	2.469	0.02 %	1.421 mA	0.0 °
C-A / c-n	10	31 348	125.0 V	50.00 Hz	2.468	2.469	0.02 %	1.894 mA	0.0 °
A-B / a-n	11	30 797	125.0 V	50.00 Hz	2.425	2.426	0.06 %	1.900 mA	0.0 °
B-C / b-n	11	30 797	125.0 V	50.00 Hz	2.425	2.426	0.06 %	1.467 mA	0.0 °
C-A / c-n	11	30 797	125.0 V	50.00 Hz	2.425	2.426	0.06 %	1.948 mA	0.0 °
A-B / a-n	12	30 245	125.0 V	50.00 Hz	2.381	2.384	0.10 %	1.952 mA	0.0 °
B-C / b-n	12	30 245	125.0 V	50.00 Hz	2.381	2.383	0.09 %	1.515 mA	0.0 °
C-A / c-n	12	30 245	125.0 V	50.00 Hz	2.381	2.383	0.09 %	2.014 mA	0.0 °
A-B / a-n	13	29 694	125.0 V	50.00 Hz	2.338	2.341	0.13 %	2.010 mA	0.0 °

Connection	Tap (P)	Tap Voltage (V)	U	Test frequency	TTR	Measured TTR	Error	I Exc	Phase
B-C / b-n	13	29 694	125.0 V	50.00 Hz	2.338	2.341	0.13 %	1.561 mA	0.0 °
C-A / c-n	13	29 694	125.0 V	50.00 Hz	2.338	2.341	0.13 %	2.075 mA	0.0 °
A-B / a-n	14	29 143	125.0 V	50.00 Hz	2.294	2.298	0.17 %	2.086 mA	0.0 °
B-C / b-n	14	29 143	125.0 V	50.00 Hz	2.294	2.298	0.17 %	1.603 mA	0.0 °
C-A / c-n	14	29 143	125.0 V	50.00 Hz	2.294	2.298	0.17 %	2.134 mA	0.0 °
A-B / a-n	15	28 591	125.0 V	50.00 Hz	2.251	2.256	0.21 %	2.155 mA	0.0 °
B-C / b-n	15	28 591	125.0 V	50.00 Hz	2.251	2.256	0.21 %	1.652 mA	0.0 °
C-A / c-n	15	28 591	125.0 V	50.00 Hz	2.251	2.256	0.21 %	2.205 mA	0.0 °
A-B / a-n	16	28 040	125.0 V	50.00 Hz	2.208	2.213	0.25 %	2.226 mA	0.0 °
B-C / b-n	16	28 040	125.0 V	50.00 Hz	2.208	2.213	0.25 %	1.706 mA	0.0 °
C-A / c-n	16	28 040	125.0 V	50.00 Hz	2.208	2.213	0.25 %	2.286 mA	0.0 °

Comment:





**SPAJ Electrical
Engineering (M) Sdn. Bhd**

RECOGNIZED AND CERTIFIED USER OF **Megger**



TRANSFORMER DC WINDING RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***




HV Winding resistance measurements

Connection	▼ Tap (P)	Current	48°C Resistance corrected to 75°C	Stability	Variation	Continuity
A-B	1	9.998 A	147.8 mΩ	98.84 %	---	✓
B-C	1	10.01 A	146.2 mΩ	99.87 %	---	✓
C-A	1	10.00 A	148.4 mΩ	98.85 %	1.51 %	✓
A-B	2	9.997 A	142.6 mΩ	99.73 %	---	✓
B-C	2	10.01 A	143.8 mΩ	99.93 %	---	✓
C-A	2	10.00 A	143.3 mΩ	99.92 %	0.86 %	✓
A-B	3	10.01 A	140.7 mΩ	99.32 %	---	✓
B-C	3	10.01 A	141.5 mΩ	99.75 %	---	✓
C-A	3	10.00 A	140.7 mΩ	99.39 %	0.61 %	✓
A-B	4	10.01 A	137.7 mΩ	99.95 %	---	✓
B-C	4	10.00 A	138.8 mΩ	99.60 %	---	✓
C-A	4	10.01 A	138.2 mΩ	99.52 %	0.82 %	✓
A-B	5	10.01 A	135.6 mΩ	99.47 %	---	✓
B-C	5	10.01 A	136.8 mΩ	99.68 %	---	✓
C-A	5	10.01 A	135.8 mΩ	99.64 %	0.89 %	✓
A-B	6	10.01 A	133.1 mΩ	99.91 %	---	✓
B-C	6	9.997 A	134.0 mΩ	99.96 %	---	✓
C-A	6	10.01 A	133.5 mΩ	99.61 %	0.68 %	✓
A-B	7	9.994 A	131.0 mΩ	99.60 %	---	✓
B-C	7	10.02 A	131.4 mΩ	98.96 %	---	✓
C-A	7	10.01 A	130.8 mΩ	99.84 %	0.45 %	✓
A-B	8	10.01 A	128.4 mΩ	99.57 %	---	✓
B-C	8	10.02 A	129.1 mΩ	99.74 %	---	✓
C-A	8	10.00 A	128.8 mΩ	99.34 %	0.56 %	✓
A-B	9	10.00 A	125.4 mΩ	99.53 %	---	✓
B-C	9	10.02 A	126.3 mΩ	99.85 %	---	✓
C-A	9	10.01 A	125.7 mΩ	99.18 %	0.69 %	✓
A-B	10	10.01 A	128.6 mΩ	99.14 %	---	✓
B-C	10	10.01 A	129.5 mΩ	99.93 %	---	✓
C-A	10	10.00 A	128.8 mΩ	99.51 %	0.68 %	✓
A-B	11	10.01 A	131.0 mΩ	99.76 %	---	✓
B-C	11	10.01 A	131.9 mΩ	99.90 %	---	✓
C-A	11	10.01 A	131.2 mΩ	99.80 %	0.67 %	✓
A-B	12	10.01 A	133.6 mΩ	99.63 %	---	✓
B-C	12	10.01 A	134.1 mΩ	99.96 %	---	✓
C-A	12	10.01 A	133.6 mΩ	99.74 %	0.42 %	✓
A-B	13	10.01 A	135.8 mΩ	99.01 %	---	✓

Connection	▼ Tap (P)	Current	48°C Resistance corrected to 75°C	Stability	Variation	Continuity
B-C	13	10.00 A	136.5 mΩ	99.73 %	---	✓
C-A	13	10.01 A	136.0 mΩ	99.73 %	0.50 %	✓
A-B	14	9.986 A	138.2 mΩ	99.02 %	---	✓
B-C	14	10.01 A	139.1 mΩ	99.80 %	---	✓
C-A	14	10.01 A	138.3 mΩ	99.77 %	0.66 %	✓
A-B	15	9.999 A	140.2 mΩ	99.83 %	---	✓
B-C	15	10.01 A	141.0 mΩ	99.39 %	---	✓
C-A	15	10.00 A	140.6 mΩ	99.46 %	0.56 %	✓
A-B	16	10.00 A	142.3 mΩ	99.77 %	---	✓
B-C	16	10.01 A	144.7 mΩ	98.85 %	---	✓
C-A	16	10.00 A	143.0 mΩ	99.86 %	1.71 %	✓


Comment:





Demag measurements

Designation	Current	Time	Remanence before demag	Remanence after demag
B-C	0.000 A	31.59 s	21.68 %	1.646 %



Comment:



LV Winding resistance measurements


Connection	▼ Tap (S)	Current	48°C Resistance corrected to 75°C	Stability	Variation
a-n	1	9.974 A	25.66 mΩ	99.55 %	---
b-n	1	10.00 A	25.28 mΩ	99.51 %	---
c-n	1	9.999 A	25.65 mΩ	99.24 %	1.51 %

Comment:



Demag measurements

Designation	Current	Time	Remanence before demag	Remanence after demag
B-C	0.000 A	28.18 s	20.10 %	<1 %



Comment:



TRANSFORMER OLTC DYNAMIC RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***



On Load Tap Changer Measurements

Software configuration


OLTC Type	Taps on	Secondary Side
Non-vacuum R	Primary	Open Circuit

Connection	Transition	t start	t	Ripple	Slope	Continuity
A-B / a-n	16 → 15	4.678 s	61.5 ms	11.70 %	9.509 A/s	✓
A-B / a-n	15 → 14	4.428 s	58.7 ms	11.12 %	9.435 A/s	✓
A-B / a-n	14 → 13	4.436 s	61.4 ms	11.34 %	9.213 A/s	✓
A-B / a-n	13 → 12	4.446 s	60.8 ms	10.95 %	9.007 A/s	✓
A-B / a-n	12 → 11	4.449 s	61.4 ms	10.77 %	8.763 A/s	✓
A-B / a-n	11 → 10	4.449 s	60.5 ms	10.39 %	8.577 A/s	✓
A-B / a-n	10 → 9	4.436 s	60.7 ms	10.25 %	8.437 A/s	✓
A-B / a-n	9 → 8	4.424 s	60.1 ms	8.552 %	7.106 A/s	✓
A-B / a-n	8 → 7	4.429 s	60.2 ms	9.641 %	8.002 A/s	✓
A-B / a-n	7 → 6	4.42 s	58.7 ms	9.333 %	7.928 A/s	✓
A-B / a-n	6 → 5	4.42 s	61.2 ms	9.565 %	7.807 A/s	✓
A-B / a-n	5 → 4	4.429 s	61 ms	9.325 %	7.629 A/s	✓
A-B / a-n	4 → 3	4.443 s	61.2 ms	9.212 %	7.512 A/s	✓
A-B / a-n	3 → 2	4.448 s	60.1 ms	8.881 %	7.368 A/s	✓
A-B / a-n	2 → 1	4.433 s	61.2 ms	8.932 %	7.291 A/s	✓
A-B / a-n	--	---	---	---	---	✓
B-C / b-n	1 → 2	4.687 s	68.3 ms	7.503 %	5.469 A/s	✓
B-C / b-n	2 → 3	4.422 s	65.9 ms	7.526 %	5.711 A/s	✓
B-C / b-n	3 → 4	4.412 s	63.9 ms	7.376 %	5.749 A/s	✓
B-C / b-n	4 → 5	4.407 s	66.9 ms	7.771 %	5.794 A/s	✓
B-C / b-n	5 → 6	4.413 s	64 ms	7.649 %	5.969 A/s	✓
B-C / b-n	6 → 7	4.419 s	63.7 ms	7.550 %	5.908 A/s	✓
B-C / b-n	7 → 8	4.421 s	65.2 ms	7.930 %	6.075 A/s	✓
B-C / b-n	8 → 9	4.415 s	65.1 ms	8.090 %	6.188 A/s	✓
B-C / b-n	9 → 10	4.41 s	63.9 ms	9.701 %	7.583 A/s	✓
B-C / b-n	10 → 11	4.416 s	66.9 ms	8.457 %	6.299 A/s	✓
B-C / b-n	11 → 12	4.401 s	63.1 ms	8.412 %	6.661 A/s	✓
B-C / b-n	12 → 13	4.402 s	66.5 ms	8.875 %	6.668 A/s	✓
B-C / b-n	13 → 14	4.4 s	66.3 ms	8.946 %	6.730 A/s	✓
B-C / b-n	14 → 15	4.41 s	62.9 ms	8.710 %	6.915 A/s	✓
B-C / b-n	15 → 16	4.402 s	65.2 ms	9.135 %	6.991 A/s	✓
B-C / b-n	--	---	---	---	---	✓
C-A / c-n	16 → 15	4.676 s	61.8 ms	11.64 %	9.408 A/s	✓
C-A / c-n	15 → 14	4.412 s	61 ms	11.25 %	9.208 A/s	✓
C-A / c-n	14 → 13	4.416 s	61.1 ms	11.06 %	9.037 A/s	✓
C-A / c-n	13 → 12	4.441 s	61.4 ms	10.88 %	8.846 A/s	✓
C-A / c-n	12 → 11	4.445 s	60.8 ms	10.55 %	8.664 A/s	✓
C-A / c-n	11 → 10	4.446 s	61 ms	10.36 %	8.479 A/s	✓
C-A / c-n	10 → 9	4.446 s	60.8 ms	10.15 %	8.340 A/s	✓
C-A / c-n	9 → 8	4.421 s	60.1 ms	8.369 %	6.928 A/s	✓


Connection	▲ Transition	t start	t	Ripple	Slope	Continuity
C-A / c-n	8 → 7	4.415 s	61 ms	9.615 %	7.851 A/s	✓
C-A / c-n	7 → 6	4.413 s	60.8 ms	9.452 %	7.765 A/s	✓
C-A / c-n	6 → 5	4.433 s	60.8 ms	9.303 %	7.645 A/s	✓
C-A / c-n	5 → 4	4.435 s	61.3 ms	9.241 %	7.527 A/s	✓
C-A / c-n	4 → 3	4.441 s	60.5 ms	9.033 %	7.459 A/s	✓
C-A / c-n	3 → 2	4.436 s	61.5 ms	8.964 %	7.274 A/s	✓
C-A / c-n	2 → 1	4.435 s	60.5 ms	8.759 %	7.236 A/s	✓
C-A / c-n	--	---	---	---	---	✓
48°C Resistance corrected to 75°C						
Connection	▲ Tap (P)	Tap Voltage (V)	Current		Stability	Variation
A-B / a-n	16	28 040	5.000 A	143.9 mΩ	99.14 %	---
A-B / a-n	15	28 591	5.000 A	140.6 mΩ	99.98 %	---
A-B / a-n	14	29 143	5.000 A	138.3 mΩ	99.71 %	---
A-B / a-n	13	29 694	5.000 A	135.9 mΩ	99.76 %	---
A-B / a-n	12	30 245	5.000 A	133.6 mΩ	99.70 %	---
A-B / a-n	11	30 797	5.000 A	131.2 mΩ	99.77 %	---
A-B / a-n	10	31 348	5.000 A	128.8 mΩ	99.83 %	---
A-B / a-n	9	31 899	5.000 A	125.7 mΩ	99.95 %	---
A-B / a-n	8	32 451	5.000 A	128.7 mΩ	99.97 %	---
A-B / a-n	7	33 002	5.000 A	131.2 mΩ	99.57 %	---
A-B / a-n	6	33 553	5.000 A	133.7 mΩ	99.70 %	---
A-B / a-n	5	34 105	5.000 A	135.9 mΩ	99.72 %	---
A-B / a-n	4	34 656	5.000 A	138.4 mΩ	99.61 %	---
A-B / a-n	3	35 207	5.000 A	140.7 mΩ	99.70 %	---
A-B / a-n	2	35 759	4.999 A	143.1 mΩ	99.82 %	---
A-B / a-n	1	36 310	5.000 A	145.3 mΩ	99.93 %	---
B-C / b-n	1	36 310	5.000 A	148.8 mΩ	98.76 %	---
B-C / b-n	2	35 759	5.000 A	143.3 mΩ	99.90 %	---
B-C / b-n	3	35 207	5.000 A	140.7 mΩ	99.69 %	---
B-C / b-n	4	34 656	4.999 A	138.3 mΩ	99.79 %	---
B-C / b-n	5	34 105	5.000 A	135.9 mΩ	99.73 %	---
B-C / b-n	6	33 553	5.000 A	133.6 mΩ	99.81 %	---
B-C / b-n	7	33 002	5.000 A	131.2 mΩ	99.67 %	---
B-C / b-n	8	32 451	5.000 A	128.7 mΩ	99.70 %	---
B-C / b-n	9	31 899	5.000 A	125.7 mΩ	99.91 %	---
B-C / b-n	10	31 348	5.000 A	128.7 mΩ	99.81 %	---
B-C / b-n	11	30 797	5.000 A	131.2 mΩ	99.82 %	---
B-C / b-n	12	30 245	5.000 A	133.6 mΩ	99.96 %	---
B-C / b-n	13	29 694	5.000 A	136.0 mΩ	99.91 %	---

Connection	▲ Tap (P)	Tap Voltage (V)	Current	48°C Resistance corrected to 75°C	Stability	Variation
B-C / b-n	14	29 143	5.000 A	138.2 mΩ	99.94 %	---
B-C / b-n	15	28 591	5.001 A	140.6 mΩ	99.97 %	---
B-C / b-n	16	28 040	5.000 A	143.0 mΩ	99.80 %	---
C-A / c-n	16	28 040	5.000 A	143.9 mΩ	99.25 %	0.63 %
C-A / c-n	15	28 591	5.000 A	140.8 mΩ	99.97 %	0.12 %
C-A / c-n	14	29 143	5.000 A	138.3 mΩ	99.68 %	0.08 %
C-A / c-n	13	29 694	5.000 A	136.1 mΩ	99.81 %	0.12 %
C-A / c-n	12	30 245	5.000 A	133.7 mΩ	99.69 %	0.12 %
C-A / c-n	11	30 797	5.000 A	131.3 mΩ	99.71 %	0.10 %
C-A / c-n	10	31 348	5.000 A	128.8 mΩ	99.54 %	0.09 %
C-A / c-n	9	31 899	5.000 A	125.7 mΩ	99.98 %	0.03 %
C-A / c-n	8	32 451	5.000 A	128.8 mΩ	99.95 %	0.09 %
C-A / c-n	7	33 002	5.000 A	131.3 mΩ	99.34 %	0.11 %
C-A / c-n	6	33 553	5.000 A	133.5 mΩ	99.68 %	0.09 %
C-A / c-n	5	34 105	5.000 A	136.1 mΩ	99.58 %	0.16 %
C-A / c-n	4	34 656	5.000 A	138.4 mΩ	99.72 %	0.03 %
C-A / c-n	3	35 207	4.999 A	140.7 mΩ	99.65 %	0.02 %
C-A / c-n	2	35 759	5.000 A	143.1 mΩ	99.59 %	0.18 %
C-A / c-n	1	36 310	5.000 A	145.4 mΩ	99.01 %	2.40 %


WRM




Ripple




Slope




Dynamic Current



Dynamic Current



Dynamic Current



Comment:



**SPAJ Electrical
Engineering (M) Sdn. Bhd**

RECOGNIZED AND CERTIFIED USER OF **Megger**



TRANSFORMER INSULATION RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***



SPAJ Electrical
Engineering (M) Sdn. Bhd.

TEST CERTIFICATE
POWER TRANSFORMER TEST

RECOGNIZED AND CERTIFIED USER OF **Megger**

Client : TENAGA NASIONAL BERHAD	Main Contractor : MALAYSIA TRANSFORMER MANUFACTURING SDN BHD
Station : PPU MALAYSINO	Manufacture year: 2010
Circuit : 33/22KV MTM TRANSFORMER :2	Serial No.: 30001
BAY ID: TX2	

INSULATION RESISTANCE & POLIRIZATION TEST

For Tr. Winding

1. 5kV Megger Insulation Reading

1) TNB Standards Insulation = 1 G OHMS

2) Polarization Index = (R 10 M/ R1M)

BEFORE SERVICE:

MAINTANANCE :

TRANSFORMER INSULATION

1 Min Reading :

10 Min Reading :

Polarization
Index > 1.2

HV To E : 535 MΩ

HV To E : 650 MΩ

1.214953

LV To E : 420 MΩ

LV To E : 510 MΩ

1.214286

HVTo LV: 420 MΩ

HVTo LV: 520 MΩ

1.238095

NOTE: AMBIENT TEMPERATURE: 36 °C

OIL TEMPERATURE: 48 °C

TIME : 10.40 AM

Tested by:	Witnessed by:	Verified by :	ESE COMMENT:
Name: VICKNESH Dept: Tester	Name: Mr. ARIF Dept: TNB	Name: Dept:	
Date: 28/09/2024	Date: 28/09/2024	Date: 28/09/2024	

TRANSFORMER TESTING REPORTS

Location: PPU MALAYSINO

Job: T2 AFTER SERVICE

Date: 28/09/2024

TRANSFORMER NO	:	02
SERIAL NO	:	30001
VOLTAGE	:	33000/22000
KVA	:	30000
MANUFACTURE	:	MTM
YEAR	:	2010
TESTING DATE	:	28/09/2024

TEST PERFORMED

S.NO .	TITLE
1	TANDELTA WINDING
2	EXCITATION CURRENT 10KV
3	TURN RATIO MEASUREMENT
4	DC WINDING RESISTANCE
5	OLTC DYNAMIC CURRENT MEASUREMENT
6	INSULATION RESISTANCE / POLARIZATION INDEX

TEST EQUIPMENT USED :

1. MEGGER TDX 120
2. MEGGER TRAX 220
3. MEGGER MIT515 INSULATION TESTER,

TESTING PERFORMED BY:

1. VICKNESH A/L SUBRAMANIAM
2. GOBINATH RAJU
3. SAKTHI




TRANSFORMER TANDELTA TEST REPORT


SPAJ Electrical
Engineering (M) Sdn. Bhd.



Tan Delta - Power Transformer

Designation	Test Mode	f (Hz)	U	I eq	C	%TD at 34 °C	ITC2 Corr. Factor	Corr. %TD to 20°C	P eq at 34 °C	% VDF	ITC2
CHG + CHL	GST-GND	50.00	10.00 kV	45.44 mA	14.46 nF	0.246	1.067	0.262	1.117 W	0.01 %	
CHG	GSTg-RB	50.00	10.01 kV	7.726 mA	2.459 nF	0.465	1.067	0.496	359.0 mW	0.02 %	●
CHL	UST-R	50.00	10.01 kV	37.72 mA	12.01 nF	0.200	1.067	0.213	753.4 mW	0.01 %	
CLG + CLH	GST-GND	50.00	6.001 kV	61.73 mA	19.65 nF	0.267	1.067	0.285	1.647 W	0.01 %	
CLG	GSTg-RB	50.00	6.006 kV	24.02 mA	7.644 nF	0.374	1.067	0.399	897.8 mW	0.02 %	
CLH	UST-R	50.00	6.007 kV	37.72 mA	12.01 nF	0.199	1.067	0.212	750.0 mW	0.01 %	





Comment:



TRANSFORMER EXCITATION 10KV TEST REPORT

SPAJ Electrical
Engineering (M) Sdn. Bhd.



Tan Delta - Power Transformer Excitation

Connection	Tap	Tap Voltage (V)	f (Hz)	U	I eq	L	P eq at 36 °C
A-B	1	36 310	50.00	9.992 kV	69.15 mA	749.4 H	545.6 W
B-C	1	36 310	50.00	10.02 kV	29.94 mA	1.838 kH	244.2 W
C-A	1	36 310	50.00	10.01 kV	66.13 mA	816.9 H	534.3 W
A-B	2	35 759	50.00	10.03 kV	70.47 mA	736.0 H	556.4 W
B-C	2	35 759	50.00	9.973 kV	30.63 mA	1.804 kH	250.4 W
C-A	2	35 759	50.00	9.966 kV	67.54 mA	799.4 H	545.5 W
A-B	3	35 207	50.00	10.06 kV	72.04 mA	720.8 H	569.1 W
B-C	3	35 207	50.00	10.02 kV	31.29 mA	1.780 kH	256.7 W
C-A	3	35 207	50.00	9.969 kV	69.11 mA	783.4 H	559.0 W
A-B	4	34 656	50.00	9.966 kV	74.05 mA	702.2 H	585.6 W
B-C	4	34 656	50.00	10.03 kV	32.02 mA	1.750 kH	263.6 W
C-A	4	34 656	50.00	10.03 kV	70.63 mA	770.3 H	572.8 W
A-B	5	34 105	50.00	9.963 kV	75.97 mA	686.3 H	601.7 W
B-C	5	34 105	50.00	10.03 kV	32.82 mA	1.724 kH	271.4 W
C-A	5	34 105	50.00	10.04 kV	72.42 mA	754.9 H	588.8 W
A-B	6	33 553	50.00	9.960 kV	77.96 mA	671.4 H	618.8 W
B-C	6	33 553	50.00	9.985 kV	33.74 mA	1.689 kH	279.9 W
C-A	6	33 553	50.00	9.981 kV	74.42 mA	737.4 H	606.3 W
A-B	7	33 002	50.00	10.03 kV	79.82 mA	660.5 H	636.3 W
B-C	7	33 002	50.00	9.970 kV	34.69 mA	1.662 kH	289.3 W
C-A	7	33 002	50.00	9.967 kV	76.45 mA	722.5 H	624.8 W
A-B	8	32 451	50.00	9.986 kV	82.09 mA	645.0 H	656.1 W
B-C	8	32 451	50.00	10.04 kV	35.61 mA	1.642 kH	298.7 W
C-A	8	32 451	50.00	9.963 kV	78.59 mA	706.9 H	644.1 W
A-B	9	31 899	50.00	9.980 kV	84.33 mA	631.4 H	676.0 W
B-C	9	31 899	50.00	9.966 kV	38.31 mA	1.414 kH	309.9 W
C-A	9	31 899	50.00	10.05 kV	80.57 mA	695.6 H	663.2 W
A-B	10	31 348	50.00	9.965 kV	87.78 mA	594.7 H	695.7 W
B-C	10	31 348	50.00	9.982 kV	39.24 mA	1.388 kH	318.4 W
C-A	10	31 348	50.00	10.06 kV	84.06 mA	648.4 H	682.3 W
A-B	11	30 797	50.00	10.02 kV	89.93 mA	583.7 H	715.1 W
B-C	11	30 797	50.00	10.03 kV	40.23 mA	1.365 kH	327.8 W
C-A	11	30 797	50.00	9.954 kV	86.63 mA	631.3 H	704.5 W
A-B	12	30 245	50.00	10.06 kV	92.26 mA	571.6 H	735.6 W
B-C	12	30 245	50.00	9.993 kV	41.40 mA	1.337 kH	338.6 W

Connection	Tap	Tap Voltage (V)	f (Hz)	U	I eq	L	P eq at 36 °C
C-A	12	30 245	50.00	10.03 kV	88.83 mA	620.4 H	725.2 W
A-B	13	29 694	50.00	9.991 kV	95.10 mA	556.5 H	759.8 W
B-C	13	29 694	50.00	10.04 kV	42.56 mA	1.314 kH	349.8 W
C-A	13	29 694	50.00	10.05 kV	91.34 mA	607.4 H	748.1 W
A-B	14	29 143	50.00	9.945 kV	97.93 mA	543.3 H	784.7 W
B-C	14	29 143	50.00	10.04 kV	43.88 mA	1.287 kH	362.4 W
C-A	14	29 143	50.00	9.972 kV	94.33 mA	590.7 H	774.2 W
A-B	15	28 591	50.00	10.04 kV	100.5 mA	532.0 H	807.9 W
B-C	15	28 591	50.00	9.985 kV	45.40 mA	1.258 kH	376.9 W
C-A	15	28 591	50.00	9.961 kV	97.30 mA	577.2 H	801.6 W
A-B	16	28 040	50.00	10.05 kV	103.4 mA	521.1 H	834.7 W
B-C	16	28 040	50.00	9.972 kV	47.17 mA	1.230 kH	394.4 W
C-A	16	28 040	50.00	9.986 kV	100.3 mA	565.8 H	830.0 W

Comment:



TRANSFORMER TURNS RATIO TEST REPORT

*SPAJ Electrical
Engineering (M) Sdn. Bhd.*




Turns ratio measurements

Connection	Tap (P)	Tap Voltage (V)	U	Test frequency	TTR	Measured TTR	Error	I Exc	Phase
A-B / a-n	1	36 310	125.0 V	50.00 Hz	2.859	2.853	-0.21 %	4.182 mA	0.0 °
B-C / b-n	1	36 310	125.0 V	50.00 Hz	2.859	2.853	-0.20 %	3.580 mA	0.0 °
C-A / c-n	1	36 310	125.0 V	50.00 Hz	2.859	2.853	-0.19 %	7.250 mA	-0.01 °
A-B / a-n	2	35 759	125.0 V	50.00 Hz	2.815	2.810	-0.18 %	4.296 mA	0.0 °
B-C / b-n	2	35 759	125.0 V	50.00 Hz	2.815	2.810	-0.18 %	3.668 mA	0.0 °
C-A / c-n	2	35 759	125.0 V	50.00 Hz	2.815	2.811	-0.16 %	7.394 mA	-0.01 °
A-B / a-n	3	35 207	125.0 V	50.00 Hz	2.772	2.767	-0.16 %	4.413 mA	0.0 °
B-C / b-n	3	35 207	125.0 V	50.00 Hz	2.772	2.768	-0.15 %	3.764 mA	0.0 °
C-A / c-n	3	35 207	125.0 V	50.00 Hz	2.772	2.768	-0.14 %	7.562 mA	-0.01 °
A-B / a-n	4	34 656	125.0 V	50.00 Hz	2.728	2.725	-0.13 %	4.534 mA	0.0 °
B-C / b-n	4	34 656	125.0 V	50.00 Hz	2.728	2.725	-0.13 %	3.878 mA	0.0 °
C-A / c-n	4	34 656	125.0 V	50.00 Hz	2.728	2.725	-0.11 %	7.746 mA	-0.01 °
A-B / a-n	5	34 105	125.0 V	50.00 Hz	2.685	2.682	-0.11 %	4.663 mA	0.0 °
B-C / b-n	5	34 105	125.0 V	50.00 Hz	2.685	2.682	-0.10 %	3.999 mA	0.0 °
C-A / c-n	5	34 105	125.0 V	50.00 Hz	2.685	2.683	-0.08 %	7.927 mA	-0.01 °
A-B / a-n	6	33 553	125.0 V	50.00 Hz	2.642	2.640	-0.08 %	4.795 mA	0.0 °
B-C / b-n	6	33 553	125.0 V	50.00 Hz	2.642	2.640	-0.07 %	4.118 mA	0.0 °
C-A / c-n	6	33 553	125.0 V	50.00 Hz	2.642	2.640	-0.05 %	8.106 mA	-0.01 °
A-B / a-n	7	33 002	125.0 V	50.00 Hz	2.598	2.597	-0.05 %	4.940 mA	0.0 °
B-C / b-n	7	33 002	125.0 V	50.00 Hz	2.598	2.597	-0.04 %	4.234 mA	0.0 °
C-A / c-n	7	33 002	125.0 V	50.00 Hz	2.598	2.598	-0.02 %	8.316 mA	-0.01 °
A-B / a-n	8	32 451	125.0 V	50.00 Hz	2.555	2.554	-0.02 %	5.088 mA	0.0 °
B-C / b-n	8	32 451	125.0 V	50.00 Hz	2.555	2.555	-0.01 %	4.359 mA	0.0 °
C-A / c-n	8	32 451	125.0 V	50.00 Hz	2.555	2.555	0.01 %	8.539 mA	-0.01 °
A-B / a-n	9	31 899	125.0 V	50.00 Hz	2.511	2.512	0.02 %	5.247 mA	0.0 °
B-C / b-n	9	31 899	125.0 V	50.00 Hz	2.511	2.512	0.02 %	4.523 mA	0.0 °
C-A / c-n	9	31 899	125.0 V	50.00 Hz	2.511	2.512	0.04 %	8.748 mA	-0.01 °
A-B / a-n	10	31 348	125.0 V	50.00 Hz	2.468	2.469	0.05 %	5.397 mA	0.0 °
B-C / b-n	10	31 348	125.0 V	50.00 Hz	2.468	2.469	0.06 %	4.657 mA	0.0 °
C-A / c-n	10	31 348	125.0 V	50.00 Hz	2.468	2.470	0.07 %	8.955 mA	-0.01 °
A-B / a-n	11	30 797	125.0 V	50.00 Hz	2.425	2.427	0.09 %	5.573 mA	0.0 °
B-C / b-n	11	30 797	125.0 V	50.00 Hz	2.425	2.427	0.09 %	4.802 mA	0.0 °
C-A / c-n	11	30 797	125.0 V	50.00 Hz	2.425	2.427	0.11 %	9.205 mA	-0.01 °
A-B / a-n	12	30 245	125.0 V	50.00 Hz	2.381	2.384	0.12 %	5.760 mA	0.0 °
B-C / b-n	12	30 245	125.0 V	50.00 Hz	2.381	2.384	0.13 %	4.961 mA	0.0 °
C-A / c-n	12	30 245	125.0 V	50.00 Hz	2.381	2.385	0.14 %	9.487 mA	-0.01 °
A-B / a-n	13	29 694	125.0 V	50.00 Hz	2.338	2.342	0.16 %	5.957 mA	0.0 °
B-C / b-n	13	29 694	125.0 V	50.00 Hz	2.338	2.342	0.16 %	5.130 mA	0.0 °

Connection	Tap (P)	Tap Voltage (V)	U	Test frequency	TTR	Measured TTR	Error	I Exc	Phase
C-A / c-n	13	29 694	125.0 V	50.00 Hz	2.338	2.342	0.18 %	9.767 mA	-0.01 °
A-B / a-n	14	29 143	125.0 V	50.00 Hz	2.294	2.299	0.20 %	6.160 mA	0.0 °
B-C / b-n	14	29 143	125.0 V	50.00 Hz	2.294	2.299	0.20 %	5.309 mA	0.0 °
C-A / c-n	14	29 143	125.0 V	50.00 Hz	2.294	2.299	0.22 %	10.05 mA	-0.01 °
A-B / a-n	15	28 591	125.0 V	50.00 Hz	2.251	2.256	0.24 %	6.377 mA	0.0 °
B-C / b-n	15	28 591	125.0 V	50.00 Hz	2.251	2.256	0.24 %	5.495 mA	0.0 °
C-A / c-n	15	28 591	125.0 V	50.00 Hz	2.251	2.257	0.25 %	10.38 mA	-0.01 °
A-B / a-n	16	28 040	125.0 V	50.00 Hz	2.208	2.214	0.28 %	6.595 mA	0.0 °
B-C / b-n	16	28 040	125.0 V	50.00 Hz	2.208	2.214	0.28 %	5.693 mA	0.0 °
C-A / c-n	16	28 040	125.0 V	50.00 Hz	2.208	2.214	0.30 %	10.71 mA	-0.01 °

Comment:





**SPAJ Electrical
Engineering (M) Sdn. Bhd**

RECOGNIZED AND CERTIFIED USER OF **Megger**



TRANSFORMER DC WINDING RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***




HV Winding resistance measurements

Connection	▼ Tap (P)	Current	34°C Resistance corrected to 75°C	Stability	Variation	Continuity
A-B	1	10.00 A	148.2 mΩ	99.12 %	---	✓
B-C	1	9.992 A	147.5 mΩ	99.93 %	---	✓
C-A	1	10.00 A	148.3 mΩ	99.39 %	0.51 %	✓
A-B	2	9.980 A	144.9 mΩ	99.49 %	---	✓
B-C	2	10.00 A	144.5 mΩ	99.38 %	---	✓
C-A	2	10.00 A	144.6 mΩ	99.53 %	0.28 %	✓
A-B	3	9.996 A	142.0 mΩ	99.46 %	---	✓
B-C	3	10.02 A	142.9 mΩ	99.87 %	---	✓
C-A	3	10.00 A	141.9 mΩ	99.43 %	0.64 %	✓
A-B	4	10.01 A	139.5 mΩ	99.77 %	---	✓
B-C	4	10.01 A	140.1 mΩ	99.84 %	---	✓
C-A	4	10.00 A	139.7 mΩ	99.82 %	0.47 %	✓
A-B	5	10.03 A	136.3 mΩ	99.04 %	---	✓
B-C	5	10.01 A	137.4 mΩ	99.61 %	---	✓
C-A	5	10.00 A	137.2 mΩ	99.96 %	0.84 %	✓
A-B	6	9.990 A	135.8 mΩ	99.20 %	---	✓
B-C	6	10.00 A	135.0 mΩ	99.60 %	---	✓
C-A	6	10.01 A	134.7 mΩ	99.71 %	0.80 %	✓
A-B	7	10.01 A	132.5 mΩ	99.86 %	---	✓
B-C	7	10.00 A	132.8 mΩ	99.88 %	---	✓
C-A	7	10.01 A	132.3 mΩ	99.70 %	0.38 %	✓
A-B	8	10.00 A	129.9 mΩ	99.80 %	---	✓
B-C	8	9.998 A	130.6 mΩ	99.94 %	---	✓
C-A	8	10.00 A	130.0 mΩ	99.64 %	0.57 %	✓
A-B	9	9.990 A	126.5 mΩ	99.65 %	---	✓
B-C	9	10.02 A	127.1 mΩ	99.94 %	---	✓
C-A	9	10.00 A	126.9 mΩ	99.21 %	0.47 %	✓
A-B	10	10.01 A	130.1 mΩ	99.99 %	---	✓
B-C	10	9.981 A	130.7 mΩ	99.67 %	---	✓
C-A	10	10.00 A	129.8 mΩ	99.77 %	0.70 %	✓
A-B	11	9.989 A	132.8 mΩ	99.97 %	---	✓
B-C	11	9.996 A	133.0 mΩ	99.86 %	---	✓
C-A	11	10.01 A	132.5 mΩ	99.81 %	0.39 %	✓
A-B	12	10.01 A	134.5 mΩ	99.64 %	---	✓
B-C	12	10.01 A	135.3 mΩ	99.88 %	---	✓
C-A	12	10.01 A	134.9 mΩ	99.78 %	0.57 %	✓
A-B	13	10.01 A	137.2 mΩ	99.77 %	---	✓

Connection	▼ Tap (P)	Current	34°C Resistance corrected to 75°C	Stability	Variation	Continuity
B-C	13	10.02 A	138.1 mΩ	99.87 %	---	✓
C-A	13	10.00 A	137.2 mΩ	99.85 %	0.65 %	✓
A-B	14	10.00 A	139.5 mΩ	99.71 %	---	✓
B-C	14	10.01 A	140.0 mΩ	99.93 %	---	✓
C-A	14	10.00 A	139.7 mΩ	99.83 %	0.37 %	✓
A-B	15	10.00 A	142.0 mΩ	99.61 %	---	✓
B-C	15	10.01 A	142.5 mΩ	99.78 %	---	✓
C-A	15	10.00 A	142.0 mΩ	99.57 %	0.37 %	✓
A-B	16	10.00 A	144.2 mΩ	99.93 %	---	✓
B-C	16	10.00 A	145.4 mΩ	99.53 %	---	✓
C-A	16	10.01 A	144.1 mΩ	99.98 %	0.89 %	✓


Comment:





Demag measurements

Designation	Current	Time	Remanence before demag	Remanence after demag
B-C	0.000 A	28.91 s	21.28 %	<1 %



Comment:



LV Winding resistance measurement

Connection	Tap (S)	Current	34°C Resistance corrected to 75°C	Stability	Variation
a-n	1	9.988 A	25.67 mΩ	99.77 %	---
b-n	1	9.987 A	25.70 mΩ	99.80 %	---
c-n	1	9.999 A	25.93 mΩ	99.37 %	1.02 %

Comment:



Demag measurements

Designation	Current	Time	Remanence before demag	Remanence after demag
B-C	0.000 A	31.71 s	19.87 %	1.865 %



Comment:



TRANSFORMER OLTC DYNAMIC RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***



On Load Tap Changer Measurements


Software configuration

OLTC Type		Taps on		Secondary Side		
Non-vacuum R		Primary		Open Circuit		
Connection	Transition	t start	t	Ripple	Slope	Continuity
A-B / a-n	16 → 15	4.729 s	62 ms	11.87 %	9.571 A/s	✓
A-B / a-n	15 → 14	4.49 s	62.1 ms	11.74 %	9.537 A/s	✓
A-B / a-n	14 → 13	4.515 s	61.7 ms	11.33 %	9.170 A/s	✓
A-B / a-n	13 → 12	4.497 s	60.7 ms	11.03 %	9.079 A/s	✓
A-B / a-n	12 → 11	4.49 s	61.5 ms	10.83 %	8.787 A/s	✓
A-B / a-n	11 → 10	4.482 s	61.5 ms	10.72 %	8.741 A/s	✓
A-B / a-n	10 → 9	4.494 s	61.7 ms	10.37 %	8.339 A/s	✓
A-B / a-n	9 → 8	4.498 s	61.1 ms	8.860 %	7.221 A/s	✓
A-B / a-n	8 → 7	4.48 s	62 ms	9.904 %	7.962 A/s	✓
A-B / a-n	7 → 6	4.489 s	62.1 ms	9.738 %	7.813 A/s	✓
A-B / a-n	6 → 5	4.483 s	62.7 ms	9.688 %	7.738 A/s	✓
A-B / a-n	5 → 4	4.484 s	60.9 ms	9.249 %	7.523 A/s	✓
A-B / a-n	4 → 3	4.494 s	61.4 ms	9.241 %	7.544 A/s	✓
A-B / a-n	3 → 2	4.495 s	61.3 ms	9.150 %	7.483 A/s	✓
A-B / a-n	2 → 1	4.495 s	61.9 ms	8.992 %	7.246 A/s	✓
A-B / a-n	--	---	---	---	---	✓
B-C / b-n	1 → 2	4.615 s	63.9 ms	7.321 %	5.706 A/s	✓
B-C / b-n	2 → 3	4.371 s	65 ms	7.337 %	5.609 A/s	✓
B-C / b-n	3 → 4	4.369 s	63.9 ms	7.404 %	5.767 A/s	✓
B-C / b-n	4 → 5	4.359 s	62 ms	7.415 %	5.971 A/s	✓
B-C / b-n	5 → 6	4.364 s	63 ms	7.477 %	5.930 A/s	✓
B-C / b-n	6 → 7	4.37 s	63 ms	7.583 %	5.993 A/s	✓
B-C / b-n	7 → 8	4.363 s	62.2 ms	7.818 %	6.306 A/s	✓
B-C / b-n	8 → 9	4.362 s	62.5 ms	7.792 %	6.194 A/s	✓
B-C / b-n	9 → 10	4.36 s	62.3 ms	9.442 %	7.535 A/s	✓
B-C / b-n	10 → 11	4.368 s	66.9 ms	8.404 %	6.250 A/s	✓
B-C / b-n	11 → 12	4.372 s	63.8 ms	8.369 %	6.527 A/s	✓
B-C / b-n	12 → 13	4.356 s	63.1 ms	8.516 %	6.725 A/s	✓
B-C / b-n	13 → 14	4.357 s	63.6 ms	8.776 %	6.911 A/s	✓
B-C / b-n	14 → 15	4.357 s	64 ms	8.716 %	6.762 A/s	✓
B-C / b-n	15 → 16	4.369 s	62.5 ms	8.901 %	7.096 A/s	✓
B-C / b-n	--	---	---	---	---	✓
C-A / c-n	16 → 15	4.737 s	64.2 ms	12.21 %	9.497 A/s	✓
C-A / c-n	15 → 14	4.476 s	63.1 ms	11.90 %	9.431 A/s	✓
C-A / c-n	14 → 13	4.481 s	61.4 ms	11.36 %	9.242 A/s	✓
C-A / c-n	13 → 12	4.477 s	61.8 ms	11.16 %	9.018 A/s	✓
C-A / c-n	12 → 11	4.471 s	61.7 ms	10.93 %	8.841 A/s	✓
C-A / c-n	11 → 10	4.473 s	61.8 ms	10.71 %	8.653 A/s	✓
C-A / c-n	10 → 9	4.474 s	62.8 ms	10.58 %	8.417 A/s	✓
C-A / c-n	9 → 8	4.474 s	61.6 ms	8.949 %	7.254 A/s	✓
C-A / c-n	8 → 7	4.461 s	63.1 ms	10.15 %	8.028 A/s	✓


Connection	▲ Transition	t start	t	Ripple	Slope	Continuity
C-A / c-n	7 → 6	4.457 s	62.9 ms	9.947 %	7.902 A/s	✓
C-A / c-n	6 → 5	4.46 s	61.9 ms	9.621 %	7.765 A/s	✓
C-A / c-n	5 → 4	4.471 s	61.5 ms	9.445 %	7.660 A/s	✓
C-A / c-n	4 → 3	4.478 s	61.4 ms	9.301 %	7.562 A/s	✓
C-A / c-n	3 → 2	4.47 s	61.7 ms	9.223 %	7.471 A/s	✓
C-A / c-n	2 → 1	4.46 s	62.8 ms	9.143 %	7.268 A/s	✓
C-A / c-n	--	---	---	---	---	✓
32°C Resistance corrected to 75°C						
Connection	▲ Tap (P)	Tap Voltage (V)	Current		Stability	Variation
A-B / a-n	16	28 040	5.001 A	145.6 mΩ	99.66 %	---
A-B / a-n	15	28 591	4.999 A	142.7 mΩ	99.95 %	---
A-B / a-n	14	29 143	5.003 A	140.7 mΩ	99.93 %	---
A-B / a-n	13	29 694	5.004 A	138.2 mΩ	99.88 %	---
A-B / a-n	12	30 245	5.000 A	136.0 mΩ	99.93 %	---
A-B / a-n	11	30 797	5.001 A	134.0 mΩ	99.53 %	---
A-B / a-n	10	31 348	4.993 A	131.1 mΩ	99.98 %	---
A-B / a-n	9	31 899	5.000 A	127.8 mΩ	99.84 %	---
A-B / a-n	8	32 451	5.014 A	131.2 mΩ	99.77 %	---
A-B / a-n	7	33 002	5.007 A	133.0 mΩ	99.94 %	---
A-B / a-n	6	33 553	5.004 A	136.0 mΩ	99.65 %	---
A-B / a-n	5	34 105	4.999 A	138.3 mΩ	99.87 %	---
A-B / a-n	4	34 656	5.000 A	140.7 mΩ	99.95 %	---
A-B / a-n	3	35 207	5.003 A	143.0 mΩ	99.81 %	---
A-B / a-n	2	35 759	5.000 A	145.6 mΩ	99.60 %	---
A-B / a-n	1	36 310	5.000 A	148.0 mΩ	100.0 %	---
B-C / b-n	1	36 310	5.000 A	150.2 mΩ	99.75 %	---
B-C / b-n	2	35 759	5.000 A	146.2 mΩ	99.76 %	---
B-C / b-n	3	35 207	5.000 A	143.8 mΩ	99.76 %	---
B-C / b-n	4	34 656	5.000 A	142.3 mΩ	99.83 %	---
B-C / b-n	5	34 105	4.992 A	137.9 mΩ	99.19 %	---
B-C / b-n	6	33 553	5.000 A	136.6 mΩ	99.64 %	---
B-C / b-n	7	33 002	4.993 A	133.7 mΩ	99.85 %	---
B-C / b-n	8	32 451	4.994 A	131.7 mΩ	99.70 %	---
B-C / b-n	9	31 899	5.000 A	128.8 mΩ	99.28 %	---
B-C / b-n	10	31 348	5.000 A	131.6 mΩ	99.81 %	---
B-C / b-n	11	30 797	5.002 A	133.9 mΩ	99.53 %	---
B-C / b-n	12	30 245	5.000 A	136.7 mΩ	99.70 %	---
B-C / b-n	13	29 694	4.997 A	138.6 mΩ	99.71 %	---
B-C / b-n	14	29 143	4.988 A	141.5 mΩ	99.59 %	---
B-C / b-n	15	28 591	5.002 A	143.9 mΩ	99.76 %	---

Connection	▲ Tap (P)	Tap Voltage (V)	Current	32°C Resistance corrected to 75°C	Stability	Variation
B-C / b-n	16	28 040	4.987 A	145.3 mΩ	99.74 %	---
C-A / c-n	16	28 040	5.000 A	146.2 mΩ	99.76 %	0.63 %
C-A / c-n	15	28 591	5.000 A	143.7 mΩ	99.95 %	0.82 %
C-A / c-n	14	29 143	5.000 A	141.3 mΩ	99.96 %	0.54 %
C-A / c-n	13	29 694	5.000 A	138.9 mΩ	99.96 %	0.45 %
C-A / c-n	12	30 245	5.000 A	136.4 mΩ	99.95 %	0.55 %
C-A / c-n	11	30 797	5.000 A	134.1 mΩ	99.94 %	0.11 %
C-A / c-n	10	31 348	5.000 A	131.6 mΩ	99.96 %	0.40 %
C-A / c-n	9	31 899	5.000 A	128.4 mΩ	99.98 %	0.78 %
C-A / c-n	8	32 451	5.000 A	131.5 mΩ	99.97 %	0.32 %
C-A / c-n	7	33 002	5.000 A	134.0 mΩ	99.99 %	0.76 %
C-A / c-n	6	33 553	5.000 A	136.4 mΩ	99.93 %	0.41 %
C-A / c-n	5	34 105	5.000 A	138.8 mΩ	99.95 %	0.67 %
C-A / c-n	4	34 656	5.000 A	141.2 mΩ	99.95 %	1.07 %
C-A / c-n	3	35 207	5.000 A	143.7 mΩ	99.95 %	0.59 %
C-A / c-n	2	35 759	5.000 A	146.1 mΩ	99.97 %	0.42 %
C-A / c-n	1	36 310	5.000 A	148.4 mΩ	99.96 %	1.50 %


WRM




Ripple




Slope




Dynamic Current



Dynamic Current



Dynamic Current



Comment:



**SPAJ Electrical
Engineering (M) Sdn. Bhd**

RECOGNIZED AND CERTIFIED USER OF **Megger**



TRANSFORMER INSULATION RESISTANCE TEST REPORT

***SPAJ Electrical
Engineering (M) Sdn. Bhd.***



SPAJ Electrical
Engineering (M) Sdn. Bhd.

TEST CERTIFICATE
POWER TRANSFORMER TEST

RECOGNIZED AND CERTIFIED USER OF **Megger**

Client : TENAGA NASIONAL BERHAD	Main Contractor : MALAYSIA TRANSFORMER MANUFACTURING SDN BHD
Station : PPU MALAYSINO	Manufacture year: 2010
Circuit : 33/22KV MTM TRANSFORMER :2	Serial No.: 30001
BAY ID: TX2	

INSULATION RESISTANCE & POLIRIZATION TEST

For Tr. Winding

1. 5kV Megger Insulation Reading

1) TNB Standards Insulation = 1 G OHMS

2) Polarization Index = (R 10 M/ R1M)

AFTER SERVICE:

MAINTANANCE :

TRANSFORMER INSULATION

1 Min Reading :

10 Min Reading :

Polarization
Index > 1.2

HV To E : 640 MΩ

HV To E : 790 MΩ

1.234375

LV To E : 510 MΩ

LV To E : 620 MΩ

1.215686

HVToLV: 475 MΩ

HVToLV: 580 MΩ

1.221053

NOTE: AMBIENT TEMPERATURE: 36 °C

OIL TEMPERATURE: 40 °C

TIME : 05.40 PM

Tested by:	Witnessed by:	Verified by :	ESE COMMENT:
Name: VICKNESH Dept: Tester	Name: Mr. ARIF Dept: TNB	Name: Dept:	
Date: 28/09/2024	Date: 28/09/2024	Date: 28/09/2024	